

BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2021-22/OW/WORK_INDENT50358

APPROVED SCHEDULE - B


No.EE/BTP/BBMP/E-PMT/15/2021-22, Date: 18-02-2022

Name of Work: Emergency works in ward no. 08 Kodigehalli

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of	
				U RAMESH ()	
				In Figures	In Words
1	1346.55	Removing and resetting of footpath slab	sqm	180.0	Rupees One Hundred Eighty Only
2	16.89	Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T & P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts complete as per specifications. - reinforced cement concrete grade M20 and above	cum	1300.0	Rupees One Thousand Three Hundred Only
3	25.7	Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T & P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts complete as per specifications. - rubble stone masonry in cement mortar	cum	300.0	Rupees Three Hundred Only
4	819.47	Earth work excavation by manual means in Ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications	Cum	100.0	Rupees One Hundred Only
5	11.01	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180 Kgs using 40mm and down size graded granite metal, coarse aggregates @ 0.85 cum and fine aggregates @ 0.58cum machine mixed, concrete laid in layers not exceeding 15 cms thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications	Cum	5000.0	Rupees Five Thousand Only
6	10.28	Providing and constructing granite / trap / basalt size stone masonry in foundation cement mortar 1: 6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications. - Available stones	Cum	2800.0	Rupees Two Thousand Eight Hundred Only
7	33.78	Providing and constructing granite / trap / basalt size stone masonry in foundation cement mortar 1: 6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications. - New stones	Cum	4000.0	Rupees Four Thousand Only
8	97.92	Providing ruled pointing to coursed stone masonry with cement mortar 1:3, 20mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications with all leads and lifts etc., complete as per the direction of Engineer-in-charge of the work.	Sqm	100.0	Rupees One Hundred Only
9	11.61	Providing and laying in position plain cement concrete of mix 1:2:4 with cement at 240 kg, with 20mm and down size graded granite metal coarse aggregate at 0.69 cum and fine aggregates at 0.459 cum, machine mixed, concrete laid in layers not exceeding 15 cms thick, well compacted for coping including cost of all materials, labour, HOM of machinery, curing, complete as per specifications with all leads and lifts etc., complete as per the direction of Engineer-in-charge of the work.	Cum	5000.0	Rupees Five Thousand Only
10	73.44	Providing and laying in position reinforced cement concrete M20 mix with stone aggregates 20mm and downsize for slab (including steel reinforcement) including centering and shuttering, machine mixed, concrete laid in layers not exceeding 15cm thick well compacted cost of all materials, labour, HOM of machineries, curing complete as per specifications. - 250 mm thick	Sqm	4800.0	Rupees Four Thousand Eight Hundred Only
11	149.61	Providing and laying in position reinforced cement concrete M20 mix with stone aggregates 20mm and downsize for slab (including steel reinforcement) including centering and shuttering, machine mixed, concrete laid in layers not exceeding 15cm thick well compacted cost of all materials, labour, HOM of machineries, curing complete as per specifications. - 100 mm thick	Sqm	1821.27	Rupees One Thousand Eight Hundred Twenty One and Twenty Seven Paise Only
12	225	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications	Cum	1800.0	Rupees One Thousand Eight Hundred Only


Signature of Contractor


Executive Engineer


U.R. RAMESH ()

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rate	
				U RAMESH ()	
				In Figures	In Words
13	600	Filling Pot-holes and Patch Repairs with Bituminous Concrete, 40 mm KSRRB M3000-5. Removal of all failed material, trimming of completed excavation to provide firm vertical faces, cleaning of surface, painting of tack coat on the sides and base of excavation as per clause 500.3, filling back the pot holes with hot bituminous material as per clause 500.4, compacting, trimming and finishing the surface to form a smooth continuous surface, all as per clause 3004.2 complete as per specifications	sqm	300.0	Rupees Three Hundred Only
14	600	Supply of drinking water through water tankers of capacity 5000 litres, hiring of water tankers, hire charges of tractor 40 HP including operator and fuel, procurement of water, engaging heavy mazdoor with all leads and lifts as directed by the Engineer in charge of the work	No.	525.0	Rupees Five Hundred Twenty Five Only
15	9	RCC pipes NP2 900 mm dia including collars as directed including cost of all materials, labour, transportation, all leads and lifts etc	Rm	1800.0	Rupees One Thousand Eight Hundred Only
16	2.58	20mm jelly around dug well	Cum	700.0	Rupees Seven Hundred Only
17	4	Reinforced Cement concrete cover slab of 1.20m dia as directed including cost of all materials, labour, transportation, all leads and lifts etc concrete cover slab	No.	1800.0	Rupees One Thousand Eight Hundred Only
18	696.55	Lead for Disposal of Debris shall be payable at carriage rates by Mechanical means including loading and unloading. From 0.00 to 2.00 Km	Cum	75.0	Rupees Seventy Five Only

U. Ramesh
Signature of the Contractor

U. Ramesh
Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92
16/03

Signature of Contractor